



Due to missing symmetry properties, no UGR table can be displayed for this luminaire.





ALL DIMENSIONS ARE IN MILLIMETRES UNLESS OTHERWISE

DO NOT SCALE FROM THIS DRAWING. IF IN DOUBT ASK.

THIS DRAWING SHALL BE READ IN CONJUNCTION WITH THE PROJECT SPECIFICATION AND ALL OTHER PROJECT DOCUMENTATION.

DARK SKY CRITERIA

COMPLIANCE WITH THE LOCAL DARK SKY CRITERIA IS TO BE ACHIEVED USING PRECISE LIGHT CONTROL FROM LUMINIARE HEAD/OPTIC.

NEW LUMINAIRES INSTALLED SHALL HAVE NO UPWARD LIGHT COMPONENT IN ACCORDANCE WITH DARK SKY COMPLIANCE. THE LOCAL AUTHORITY'S DARK SKY POLICY SHALL BE CONSULTED PRIOR TO INSTALLATION OF ANY EXTERNAL LIGHTING.

CONTROL OF EXTERNAL LIGHTING SHALL BE VIA TIME CLOCK AND PHOTOCELLS. A MANUAL OVERRIDE FACILITY SHALL ALSO BE PROVIDED.

THE FOLLOWING DESIGN PRINCIPLES SHALL BE ADOPTED:

LIGHT WHAT IS NECESSARY ONLY

SKY AND ONTO NEIGHBOURING PROPERTIES.


 LIGHT THE AREAS WE NEED TO ONLY • LIGHT ONLY WHEN IT IS NECESSARY • EXTERNAL LIGHTS AND THEIR LIGHT DISTRIBUTION SHALL BE POSITIONED SO AS TO AVOID LIGHT SPILL INTO THE


ALL NEW EXTERNAL LIGHT FITTINGS FOR SIGNS AND UPLIGHTING HAVE A LUMINOUS EFFICACY OF AT LEAST 60 LAMP LUMENS/CIRCUITWATT WHEN THE LAMP WATTAGE IS GREATER THAN OR EQUAL TO 25W OR 50 LAMP LUMENS/CIRCUITWATT WHEN THE LAMP WATTAGE IS LESS

EXTERNAL LIGHT FITTINGS ARE TO BE CONTROLLED THROUGH A TIME SWITCH, OR DAYLIGHT SENSOR, TO PREVENT OPERATION DURING DAYLIGHT HOURS. DAYLIGHT SENSOR OVERRIDE ON A MANUALLY SWITCHED LIGHTING CIRCUIT IS ACCEPTABLE.

POL4; REDUCTION OF NIGHT TIME LIGHT POLLUTION

TO ENSURE THAT EXTERNAL LIGHTING IS CONCENTRATED IN THE APPROPRIATE AREAS AND THAT UPWARD LIGHTING IS MINIMISED, REDUCING UNNECESSARY LIGHT POLLUTION, ENERGY CONSUMPTION AND NUISANCE TO NEIGHBOURING PROPERTIES.





Steven A. Hunt & Associates Hangar 9, De Havilland Drive, Liverpool L24 8RN **T** 0151 427 8009 **W** www.stevenhunt.com **E** info@stevenhunt.com

Scale: 1:200 Size: A1 Drawn: BC Chkd: DK

PRELIMINARY

3836-SHA-XX-XX-DR-E-0001-S2 P1